

JEFFERSON COUNTY
BOARD OF COUNTY COMMISSIONERS



**ADDENDUM NO. 1 TO
INVITATION TO BID NO: 2024-09
GOVERNMENT FARM ROAD RESURFACING PROJECT – FROM CR 257 TO
NORTH OF PARKER POND ROAD
Issued May 16, 2024**

SECTION 1.0 SCHEDULE OF EVENTS

Failure to comply with this or any other paragraph of this RFP shall be sufficient reason for rejection of the Proposal.

All times listed in the Schedule of Events are Eastern Standard Time (EST).

<i>Event</i>	<i>Date/Time</i>
Bid Advertisement Date	April 26, 2024
Release of Invitation to Bid	April 26, 2024
Bid Questions Due from Prospective Bidder	May 10, 2024
Responses to bid questions due	May 16, 2024
BIDS DUE TO BOCC	May 29, 2024 @ 3:00 P.M.
Posting of Intended Award	May 29, 2024
Board Consideration of Intended Award	June 20, 2024
Posting of Notice of Award	June 21, 2024

This addendum is being posted to inform prospective bidders of questions received, changes to the schedule of events, & revisions to Form 2 "Basis of Bid".

1. What is the engineer budget estimate?
A: The construction budget for this project is \$622,440.00.
2. Is there any Bid bond requirements for this project? Because is not specified in the ITB
A: No, but under section 9.6.3 “The successful bidder must provide Performance and Payment Bonds in the amount of 100% of the contract amount.”
3. On page 4 of the plan set, the asphalt type indicated is SP 9.5 (76-22) **Traffic A**, however on the bid forms the bid schedule specify a Traffic B mix (Item 334-1-12). Can you please indicate what is the correct type of mix for this project?
4. A: The correct Asphalt type will be the SP 9.5 - The pay item (344-1-12) Should say SP 9.5 Type A
5. Is the pay item 120-3 Lateral Ditch Excavation to reestablish the ditch flow lane in the areas indicated on the drawings? If not, please indicate where is this for?
A: That is correct the pay item 120-3 is for reestablishing the ditch flow at the locations indicated in the plans
6. Can you please indicate what pipes are related to pay item 430-94-100 Desilting pipe?
A: This pay item will be for all the driveways that have 0-24” piping for drainage` as indicated in the plans
7. Per the cross section doesn’t look that any material needs to be excavated. Can you please verify if the quantities under Pay Item 120-1 Regular excavation are correct? Or if this is related to regrading the existing road?
A: Pay Item 120-1 is Sheet 13 on the plan view at Station 50+20 to 51+40 , The Quantities look to be correct for that area.

**BID PROPOSAL
FORM 2:
BASIS OF BID
JEFFERSON
COUNTY**

Full Company Name of Bidder: _____

Main Business Address: _____
(including city, state and zip)

Business Telephone and Fax Numbers: _____

Contact Name: _____

State Contractor's License# _____

**GOVERNMENT FARM ROAD RESURFACING PROJECT – FROM CR 257 TO NORTH OF PARKER
POND ROAD
ITB 2024-09
ADDENDUM NO. 1
Exhibit B
Basis of Bid**

Bidder will complete the Work in accordance with the Contract Agreement for the following price(s):

ROADWAY CONSTRUCTION (FPID No. 446590-1-54-01)					
PAY ITEM NUMBER	DESCRIPTION	UNIT	QUANTIT Y	UNIT PRICE	COST
GENERAL COSTS					
101-1	MOBILIZATION	LS	1.00		
102-1	MAINTENANCE OF TRAFFIC	LS	1.00		
110-1-1	CLEARING & GRUBBING	LS	1.00		
<i>SUBTOTAL</i>					
ROADWAY					
120-1	REGULAR EXCAVATION	CY	300.00		
120-2-2	BORROW EXCAVATION	CY	950.00		
285-711	OPTIONAL BASE GROUP 11	SY	140.00		
286-1	TURNOUT CONSTRUCTION	SY	500.00		
332-1	6" DEPTH RECLAMATION (GRADE & SHAPE)	SY	17,800.00		
334-1-12	SUPERPAVE ASPHALTIC CONC., TRAFFIC A	TN	2,020.00		
570-1-1	PERFORMANCE TURF	SY	5,800.00		
570-1-2	PERFORMANCE TURF, SOD	SY	5,130.00		
710-11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	LF	60.00		
710-11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.50		
710-11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.50		
<i>SUBTOTAL</i>					
SIGNING & PAVEMENT MARKINGS					
700-1-11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	EA	18.00		
700-1-60	SINGLE POST SIGN, REMOVE	EA	11.00		
705-10-2	OBJECT MARKER, TYPE 2	EA	4.00		

706-1-3	RAISED PAVEMENT MARKER, TYPE B	EA	408.00		
*710-11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.30		
*710-11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	LF	60.00		
*710-11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.50		
*710-11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.50		
710-90	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.00		
711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	60.00		
711-11-160	THERMOPLASTIC, STANDARD, WHITE MESSAGE				
	STOP	EA	1.00		
711-16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.30		
711-16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.50		
711-16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.50		
				<i>SUBTOTAL</i>	
DRAINAGE IMPROVEMENTS					
104-10-3	SEDIMENT BARRIER	LF	120.00		
120-2-2	BORROW EXCAVATION	CY	140.00		
120-3	LATERAL DITCH EXCAVATION	CY	530.00		
400-1-2	CONCRETE CLASS I, ENDWALLS	CY	3.00		
430-94-100	DESILTING PIPE, 0-24"	LF	630.00		
430-175-115	PIPE CULVERT, RCP MATERIAL, ROUND 15" CD	LF	40.00		
430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	2.00		
570-1-2	PERFORMANCE TURF, SOD	SY	140.00		
				<i>SUBTOTAL</i>	
				TOTAL	