

JEFFERSON COUNTY HISTORIC HIGH SCHOOL

Hurricane Michael Grant - Restoration

SCOPE OF WORK

(REFERENCE DRAWINGS W/ REVISIONS DATED 04/20/23)

Careful disassembly of undamaged wood flooring and wainscoting located at the first and second floors (East wing). *These materials are to be stored at a dry location until restoration/reinstallation.*

Interior doors/door frames, transoms and hardware are to be carefully disassembled. *These materials are to be stored at a dry location until restoration/reinstallation.*

Demolition of basement, first and second level interior wood stud walls as previously executed on the west wing.

Careful disassembly of the eastern staircase, as well as other historic elements of the building in this location that are yet to be restored. *These materials are to be stored at a dry location until restoration/reinstallation.*

First and Second level wood floor joists are to be removed for access to basement floor slab in accordance with the Architectural and Structural drawings in the same manner performed on the previously restored west wing. *These materials are to be stored at a dry location until restoration/reinstallation.*

Demolition of the existing basement floor slab.

Installation of below-slab drainage system at the east basement consistent with the previously installed system at the west basement in accordance with Engineer drawings.

Both East and West under-slab drainage systems shall be joined and routed in a new drainage line to the storm drain at the right of way north of the building.

A below slab helical pile/concrete foundation system will be required in accordance with the structural engineer drawings as previously installed on the west wing basement floor.